

# Delock 19" Optical Fiber Splice Box 12 x LC Duplex OM3 1U complete assembled

## Description

This pre-assembled optical fiber splice box by Delock can be mounted in a 19" rack and is ideal for quickly and securely setting up the fiber optic network in buildings.

### Complete assembled

The optical fiber box is equipped with 12 LC Duplex couplers and fitted with 24 pigtails, which are already inserted in the splice cassette.

### With drawer

The front panel can be pulled out, making it possible to work on both sides of the couplers without removing the cover.

## Note

The pigtails are not ready for splicing.



**Item no. 67004**

EAN: 4043619670048

Country of origin: China

Package: Box

## Technical details

- For mounting in 19" racks, 1U
- Splice box with 12 x LC Duplex couplers
- Extendable tray
- With splice cassette
- Fiber pigtails are coloured in accordance with TIA/EIA-598
- OM3 pigtails
- Fibre: 50/125 µm
- Cable jacket material: LSOH
- Cable length: ca. 1.5 m
- Housing colour: black
- Housing material: metal
- Dimensions (LxWxH): ca. 482 x 220 x 44 mm

## Package content

- 19" optical fiber splice box
- 4 x screw
- 4 x caged nut
- 4 x washer

## Images



## General

|                |       |
|----------------|-------|
| Mounting type: | 19 in |
|----------------|-------|

## Physical characteristics

|                   |        |
|-------------------|--------|
| Housing colour:   | black  |
| Housing material: | metal  |
| Cable length:     | 1.5 m  |
| Length:           | 482 mm |
| Width:            | 220 mm |
| Height:           | 44 mm  |